


**ANDHRA PRADESH EDUCATION & WELFARE
INFRASTRUCTURE DEVELOPMENT CORPORATION**



AGREEMENT

Name of the work : Procurement of Supply and Fixing of Ceiling Fans of 48 inches (1200MM) sweep to the Government Schools (Educational Institutions) of SPSR Nellore, Kurnool, Ananthapur, YSR Kadapa and Chittoor (5) erstwhile District as Package-III in Andhra Pradesh Under MANABADI: NADU-NEDU (Phase-II)

Name of the Agency : RR Kabel Limited,
Regd. Off: Ram Ratna House,
Utopia City, P.B Marg,
Worli, Mumbai-400013

Estimate Cost: Rs. 17.04 Crores

O/o The Managing Director,
APEWIDC, Vaddeswaram (V)
Tadepally (M), Guntur District

ANNEXURE-A
(Schedule-A)

Name of the work : Procurement of Supply and Fixing of Ceiling Fans of 48 inches (1200MM) sweep to the Government Schools (Educational Institutions) of SPSR Nellore, Kurnool, Ananthapur, YSR Kadapa and Chittoor (5) erstwhile District as Package-III in Andhra Pradesh Under MANABADI: NADU-NEDU (Phase-II)

S. No.	Est. Qty	Item	Rate in Rupees	Unit	Amount in Rupees
1	2	3	4	5	6
1	79832	<p>Supply and fixing of Ceiling Fans of 48" (1200mm) sweep Ceiling Fan at the rated voltage 230V, Rated frequency 50hz, double ball bearings, air delivery more than 210 cubic meter per minute , Speed more than 350 RPM and Power input not more than 50 Watts with all accessories with 100% copper winding , 230 voltage anti corrosion aluminum body , 3 blades with 1.08mm thickness (excluding painting) aluminum body and blades having average width of 120mm, down rod with 300mm to 450mm length & 19.2mm outer diameter Heavy Gauge , all the factors of fan shall be of corrosion resisting material or suitably and durably protected against corrosion, including cost and conveyance of all materials ,loading ,unloading, stacking at school site and fixing , inclusive of GST and all other Taxes etc., complete as applicable from time to time, and all other incidental charges etc., complete for finished item of work (As per IS : 374-1979) to the government schools in the state of Andhra Pradesh.</p> <p>sweep 1200mm Colour Ivory Test voltage 230V 50Hz I Ph. A.Cp</p>	1813	Each	14,47,35,416

Authorized Signature
of the Firm/Company

20

Managing Director
APEWIDC, Vijayawada

A
29/8/22

u
29/8/22

	Winding	100% Copper		
	Blades (thickness)	3 Nos & 1.08mm		
	thickness (excluding painting)			
	Down rod	19.2mm OD		
	Heavy Gauge with 300mm length	to 450mm		
	Additional safety wire 300mm to 450mm	1.6mm GI wire		
	locking arrangement	long with		
	Bearings	double ball		
	bearings			
	POWER (Watt)	Power input		
	not more than 50 W			
	Air delivery	Not less than		
	210 CMM			
	Speed	Not less than		
	350 RPM			
	including GST and all other taxes etc, complete as applicable from time to time			
	<u>The item shall carry warranty of 5 years from the date of completion of work of supply and fixing.</u>			
		Total		Rs. 14,47,35,416/-
Rupees Fourteen Crores Forty Seven Lakhs Thirty Five Thousand Four Hundred Sixteen Only				



Authorized Signature
of the Firm/Company

21

Managing Director
APEWIDC, Vijayawada

A
29/8/22

G
29/8/22